

Rebuilt 27" x 8.6 ft. Eagle Pugmill S/N 8926



Chassis

- Dropped 8" x 4" HSS Main Frame
- Tandem suspension
- Eight (8) 9 x 20 wheels and tires
- Access platform
- Sand blasted & painted

Rebuilt 27" x 8.6ft 200 to 350 t.p.h. Eagle Pugmill

- 40hp, 460volt, 1760rpm electric motor
- Eagle gear reducer, new gears & bearings
- Maximum Material size 2 1/2"
- 12ft x 6ft mixing tub
- New shaft, bearings, pug mill arms and paddles

New 42" x 12'-6" Discharge Conveyor


- 12" Rubber lagged head pulley c/w 2 7/16" Dodge S2000 double spherical roller bearings
- Dodge TA3203 Reducer
- 7.5 H.P. Electric motor
- 12" Self cleaning tail pulley c/w 2 7/16" NTN UCPX Ultra-Class ball bearings
- 20° 5" Troughing idlers @ 18" centres
- 5" Self cleaning return roller
- Enclosed take ups
- 3 ply 3/16" x 1/16" Goodyear Pylon Conveyor belt
- Hot vulcanized splice
- V plow

Selling Price \$115,000.00
Mthly rental \$17,000.00

Plant rebuilt in May 2009. \$73,700.00 spent on repairs.



www.elrus.com



ELRUS
AGGREGATE SYSTEMS



36 Years

1975 - 2011

email: info@elrus.com

Head Office & Manufacturing Facility
4409 Glenmore Trail, S.E., Calgary, AB T2C 2R8 (888) 535-7877